

tabela robót ziemnych

przekroje	pow I	pow II	sred	odl	objęt
12	4,44	3,89	4,165	5	20,825
23	3,89	3,73	3,81	5	19,05
34	3,73	3,56	3,645	5	18,225
45	3,56	3,5	3,53	5	17,65
56	3,5	5,02	4,26	5	21,3
67	5,02	6,28	5,65	5	28,25
78	6,28	6,26	6,27	5	31,35
89	6,26	6,21	6,235	5	31,175
910	6,21	4,03	5,12	5	25,6

łącznie pow. wykopu

213,425 m3